

ADDENDUM #1

Project: H7 Foundation Removal

Project #: 20.008

Date: July 2, 2020

Bid Date: 3:00 July 14, 2020

Addendum Description:

1. All concrete foundations located within 10' of existing railroad shall be left in place. Concrete shall be broken or cut measured 10' from the edge of railroad. All foundations beyond the 10' measurement shall be removed as indicated within the construction documents. A smooth foundation edge is not required at the 10' measurement.
2. All existing piles of demolished concrete/rebar shall be removed from site.
3. The reservoir foundations located at the northeast portion of the project area shall remain in place as indicated on the attached exhibit.

